

NOTES:

- 1. THE SDPN ENCLOSURE MUST BE EARTHED.
- 2. TO MEET EMC REQUIREMENTS THE CONTROLLER MUST BE INSTALLED ACCORDING TO THE INSTALLATION REQUIREMENTS SHEET FOR THIS PRODUCT.
- 3. INPUT REQUIRE `C' CONNECTED TO THE NEUTRAL AND THE INPUT TO 230Vac WHEN SIGNAL IS PRESENT.
- 4. CONNECTIONS TO CON2 & 3 MUST BE ON THE SAME PHASE AS THE SUPPLY ON CON 1.

 THIS UNIT IS NOT RATED FOR 415V
- 5. FROM FIRMWARE VERSION 0.00.1 PIPE SENSORS ARE SUPPORTED AS A COMMISSIONING OPTION.
- 6. THERMISTOR SENSORS AS STANDARD ARE 5K. FROM VERSION 0.00.4 2K & 2K2 TYPES ARE SUPPORTED FOR LEGACY USE.



02681

1

DRG No:

THIS IS AN UNCONTROLLED COPY - UNLESS STAMPED WITH CONTROLLED COPY STAMP